ITEM NO.	PAY ITEM	DESCRIPTION	UNIT	CONTRACT QUANTITY	PLAN SHEET TOTALS	IF & WHERE DIRECTED	AS-BUILT QUANTITY
154003P	1	Mobilization	LS	1	1		
159006M	2	Drum	UNIT	50		50	
159009M	3	Traffic Cone	UNIT	50		50	
159012M	4	Construction Signs	SF	250	232	18	
159021P	5	Construction Barrier Curb	LF	160	80	80	
201003P	6	Clearing Site	LS	1	1		
202009M	7	Excavation, Unclassified	CY	50	42	8	
302036M	8	Dense-Graded Aggregate Base Course, 6" Thick	SY	70	66		
401009M	9	HMA Milling, 3" or Less	SY	827	751		
401030M	10	Tack Coat	GAL	110	100	10	
401042M	11	Hot Mix Asphalt 9.5 M 64 Surface Course	TON	145	132	13	
401096M	12	Hot Mix Asphalt 19 M 64 Base Course	TON	21	19	2	
452003M	13	Partial Depth Concrete Repair	SY	50		50	
506004M	14	Structural Steel	LB	4,500	4,100	400	
607021P	15	9" X 18" Concrete Vertical Curb	LF	250		15	
610013M	16	Traffic Marking Lines, 4"	LF	1000		100	
610017M	17	Traffic Marking Lines, 24"	LF	400	310	90	
606012P	18	Concrete Sidewalk, 4" Thick	SY	21	19	2	
701033P	19	4" Rigid Nonmetallic Conduit	LF	75	70	5	

DELETE

FRENCH & PARRELLO ASSOCIATES
Corporate Office
1800 Route 34, Suite 101
Wall, NJ 07719
732.312.9800
Regional Offices
Camden, NJ
Hackettstown, NJ
New York, NY

1/10/20
SARAH STEIB, PE
PROFESSIONAL ENGINEER, NJ LIC. No. 24GE05012800

ESTIMATE OF QUANTITIES

FOR THE REPAIR OF
YOGI BERRA DRIVE BRIDGE
STRUCTURE No. 0760153
ON YOGI BERRA DRIVE OVER
NJ TRANSIT MONTCLAIR BOONTON LINE
IN THE TOWNSHIP OF MONTCLAIR
ESSEX COUNTY, NEW JERSEY

DATE:	DESIGNED BY:	DRAWN BY:	PROJECT NUMBER:
JANUARY 2020	DS	DS	1064.025
SCALE:	CHECKED BY:	CHECKED BY:	SHEET:
AS SHOWN	SS	SS	3 of 9

No.	Date	Revision	Revised By	Checked By

PLOTTED ON: 1/9/2020 5:17:12 PM
PLOTTED BY: DANIEL SEPTON

O:\INH\1000\1064 - MONTCLAIR STATE UNIVERSITY\1064.025 - YOGI BERRA BRIDGE REPAIR\CAD\DWG\1064.025 - COVER.DWG -- Estimate of Quantities

COPYRIGHT © 2019. FRENCH & PARRELLO ASSOCIATES - THE COPYING OR REUSE OF THIS DOCUMENT, OR PORTIONS THEREOF, WITHOUT THE WRITTEN PERMISSION OF FRENCH & PARRELLO ASSOCIATES, PA IS PROHIBITED. DUE TO INHERENT ERRORS IN REPRODUCTION METHODS, ERRORS MAY OCCUR WHEN SCALING THIS DRAWING